

**DRAFT SOUTH LANTAU COAST OUTLINE ZONING PLAN NO.**

**S/SLC/22**

Amendments

Notes

Schedule of Uses

Explanatory Statement

**SCHEDULE OF AMENDMENTS TO  
THE APPROVED SOUTH LANTAU COAST OUTLINE ZONING PLAN NO. S/SLC/21  
MADE BY THE TOWN PLANNING BOARD  
UNDER THE TOWN PLANNING ORDINANCE (Chapter 131)**

**I. Amendments to Matters shown on the Plan**

- Item A1 – Rezoning of an area in Pui O from “Coastal Protection Area” (“CPA”) and “Other Specified Uses” annotated “Water Pumping Station” (“OU(WPS)”) to “Conservation Area” (“CA”).
- Item A2 – Rezoning of an area along South Lantau Road and Chi Ma Wan Road in Pui O from “CPA” to “Recreation” (“REC”).
- Item A3 – Rezoning of an area to the south of South Lantau Road in Shui Hau from “CPA” and “Country Park” (“CP”) to “CA”.
- Item A4 – Rezoning of a site in Mong Tung Wan from “Green Belt” (“GB”) to “REC”.
- Item B1 – Rezoning of a site to the northeast Pui O Lo Wai Tsuen from “GB” and “Village Type Development” (“V”) to “OU(WPS)”.
- Item B2 – Rezoning of an area at Pui O Raw Water Pumping Station from “CPA” to “OU(WPS)”.
- Item B3 – Rezoning of three sites in Pui O from “CPA” to “Government, Institution or Community” (“G/IC”).
- Item B4 – Rezoning of four sites in Pui O, Cheung Sha and Tong Fuk from “CPA” to “Open Space” (“O”).
- Item B5 – Rezoning of a site to the north of Upper Cheung Sha Beach from “GB” to “O”.
- Item B6 – Rezoning of three sites in Pui O, Cheung Sha and Tong Fuk from “CPA” to areas shown as ‘Road’.
- Item B7 – Rezoning of a site in the southeastern part of Shui Hau Tsuen from “V” to an area shown as ‘Road’.
- Item B8 – Rezoning of three areas from “GB”, “Residential (Group C)” (“R(C)”) and “CPA” to areas shown as ‘Road’.
- Item B9 – Rezoning of two areas from “R(C)” and an area shown as ‘Road’ to “CPA”.
- Item B10 – Rezoning of an area in Cheung Sha from “CPA” to “R(C)”.
- Item B11 – Rezoning of an area in Cheung Sha from “R(C)” to “CPA”.
- Item B12 – Rezoning of a site to the north of South Lantau Road in Cheung Sha from “R(C)” to “G/IC”.

- Item B13 – Rezoning of two areas to the northeast of South Lantau Road from “GB” and “R(C)” to “G/IC”.
- Item B14 – Rezoning of an area in Cheung Sha from “R(C)” to “G/IC”.
- Item B15 – Rezoning of an area in Cheung Sha from “G/IC” to “R(C)”.
- Item B16 – Rezoning of four areas in Cheung Sha from “R(C)” and “G/IC” to “GB”.
- Item B17 – Rezoning of four areas in Cheung Sha from “GB” to “R(C)”.
- Item B18 – Rezoning of an area to the south of Catchwater Road and north of Cheung Sha from “GB” to “OU” annotated “Water Treatment Works” (“OU(WTW)”).
- Item B19 – Rezoning of a piece of land on the northern periphery of Tong Fuk Correctional Institution from “GB” to “G/IC”.
- Item B20 – Rezoning of a piece of land on the eastern periphery of Tong Fuk Correctional Institution from “G/IC” to “GB”.
- Item B21 – Rezoning four sites in Shui Hau, Shek Pik and Tai Long Wan from “GB” to “G/IC”.
- Item C1 – Rezoning an area to the south of Shui Hau Wan from “CP” to “CPA”.
- Item C2 – Rezoning an area to the south of Catchwater Road and north of Shui Hau from “GB” to “CP”.
- Item C3 – Rezoning an area to the south of South Lantau Road near Shui Hau from “CP” to “CA”.
- Item D1 – Incorporation of an area to the northwest of Fan Lau Sai Wan into the planning scheme area of the OZP and zoning it as “GB”.

## **II. Amendments to the Notes of the Plan**

- (a) Revision to the covering Notes of the extant OZP to form ‘Part A’ of the covering Notes of the draft OZP and incorporation of a new set of ‘Part B’ of covering Notes of the draft OZP.
- (b) Addition of a new set of Notes for the “O” zone.
- (c) Addition of a new set of Notes for the ‘REC’ zone.
- (d) Addition of a new set of Notes for the “OU(WTW)” zone.
- (e) Addition of a new set of Notes for the “CA” zone.
- (f) Inclusion of ‘Library’ and ‘Public Clinic’ under Column 2 and revision to planning intention in the Notes for the “R(C)” zone.

- (g) Inclusion of 'Field Study/Education/Visitor Centre' and 'Hotel (Holiday House only)' under Column 2 in the Notes for the "V" zone.
- (h) Deletion of 'Government Refuse Collection Point' and 'Public Convenience' from Column 2 and inclusion of these uses under Column 1 in the Notes for the "V" zone.
- (i) Deletion of 'Market' from Column 2 in the Notes for the "V" zone.
- (j) Inclusion of 'Animal Quarantine Centre (in Government building only)' under Column 1 and 'Animal Boarding Establishment', 'Animal Boarding Centre (not elsewhere specified)' and 'Zoo' under Column 2, and revision to planning intention in the Notes for the "G/IC" zone.
- (k) Revision of 'House (Staff Quarters only)' to 'House (other than rebuilding of New Territories Exempted House (NTEH) or replacement of existing domestic building by NTEH permitted under the covering Notes)' under Column 2 in the Notes for the "G/IC" zone.
- (l) Revision of 'Flat (Staff Quarters only)' to 'Flat' and 'Shop and Services' to 'Shop and Services (not elsewhere specified)' under Column 2 in the Notes for the "G/IC" zone.
- (m) Inclusion of 'Flat' and 'Zoo' under Column 2 and revision to planning intention in the Notes for the "GB" zone.
- (n) Revision of 'House' to 'House (other than rebuilding of New Territories Exempted House (NTEH) or replacement of existing domestic building by NTEH permitted under the covering Notes)' under Column 2 in the Notes for the "GB" zone.
- (o) Deletion of 'Barbecue Spot' from Column 2 and inclusion of this use under Column 1 in the Notes for the "GB" and "CPA" zones.
- (p) Inclusion of 'Wetland Habitat' under Column 1 and revision to planning intention in the Notes for the "CPA" zone.
- (q) Revision to the Remarks of the Notes for "GB" zone to incorporate planning permission requirement for filling of land/pond or excavation of land.
- (r) Revision to the Remarks of the Notes for "CPA" zone to incorporate planning permission requirement for filling of pond.
- (s) Revision to the Remarks of the Notes for the "CPA" zone on diversion of stream, filling of land or excavation of land.

*Town Planning Board*

*15 September 2023*

## **DRAFT SOUTH LANTAU COAST OUTLINE ZONING PLAN NO. S/SLC/22**

(Being a Draft Plan for the Purposes of the Town Planning Ordinance)

### **NOTES**

(N.B. These form part of the Plan)

**PART A** (This Part A applies to land within the boundaries of the Plan which are not within the boundaries of “regulated area” as defined in section 1A of the Town Planning Ordinance (hereafter referred to as “Regulated Area”))

- (1) These Notes show the uses or developments on land falling within the boundaries of the Plan which are always permitted and which may be permitted by the Town Planning Board, with or without conditions, on application. Where permission from the Town Planning Board for a use or development is required, the application for such permission should be made in a prescribed form. The application shall be addressed to the Secretary of the Town Planning Board, from whom the prescribed application form may be obtained.
- (2) Any use or development which is always permitted or may be permitted in accordance with these Notes must also conform to any other relevant legislation, the conditions of the Government lease concerned, and any other Government requirements, as may be applicable.
- (3)
  - (a) No action is required to make the existing use of any land or building conform to this Plan until there is a material change of use or the building is redeveloped.
  - (b) Any material change of use or any other development (except minor alteration and/or modification to the development of the land or building in respect of the existing use which is always permitted) or redevelopment must be always permitted in terms of the Plan or, if permission is required, in accordance with the permission granted by the Town Planning Board.
  - (c) For the purposes of subparagraph (a) above, “existing use of any land or building” means –
    - (i) before the publication in the Gazette of the notice of the first statutory plan covering the land or building (hereafter referred to as ‘the first plan’),
      - a use in existence before the publication of the first plan which has continued since it came into existence; or
      - a use or a change of use approved under the Buildings Ordinance which relates to an existing building; and
    - (ii) after the publication of the first plan,
      - a use permitted under a plan which was effected during the effective period of that plan and has continued since it was effected; or

- a use or a change of use approved under the Buildings Ordinance which relates to an existing building and permitted under a plan prevailing at the time when the use or change of use was approved.
- (4) Except as otherwise specified by the Town Planning Board, when a use or material change of use is effected or a development or redevelopment is undertaken, as always permitted in terms of the Plan or in accordance with a permission granted by the Town Planning Board, all permissions granted by the Town Planning Board in respect of the site of the use or material change of use or development or redevelopment shall lapse.
- (5) Road junctions, alignments of roads and boundaries between zones may be subject to minor adjustments as detailed planning proceeds.
- (6) Temporary uses (expected to be 5 years or less) of any land or buildings are always permitted as long as they comply with any other relevant legislation, the conditions of the Government lease concerned, and any other Government requirements, and there is no need for these to conform to the zoned use or these Notes. For temporary uses expected to be over 5 years, the uses must conform to the zoned use or these Notes.
- (7) The following uses or developments are always permitted on land falling within the boundaries of the Plan except where the uses or developments are specified in Column 2 of the Notes of individual zones:
- (a) provision, maintenance or repair of plant nursery, amenity planting, open space, rain shelter, refreshment kiosk, road, bus stop or lay-by, cycle track, taxi rank, nullah, public utility pipeline, electricity mast, lamp pole, telephone booth, telecommunications radio base station, automatic teller machine and shrine;
  - (b) geotechnical works, local public works, road works, sewerage works, drainage works, environmental improvement works, marine related facilities, waterworks (excluding works on service reservoir) and such other public works co-ordinated or implemented by Government;
  - (c) maintenance or repair of watercourse and grave;
  - (d) rebuilding of New Territories Exempted House; and
  - (e) replacement of an existing domestic building, i.e. a domestic building which was in existence on the date of the publication of the first plan, by a New Territories Exempted House.
- (8) In any area shown as 'Road', all uses or developments except those specified in paragraph (7) above in this Part A and that specified below require permission from the Town Planning Board:
- on-street vehicle park.
- (9) Unless otherwise specified, all building, engineering and other operations incidental to and all uses directly related and ancillary to the permitted uses and developments within the same zone are always permitted and no separate permission is required.

- (10) In these Notes,
- (a) unless the context otherwise requires or unless as expressly provided in this paragraph (10), terms used in the Notes shall have the meanings as assigned under section 1A of the Town Planning Ordinance.
  - (b) “existing building” means a building, including a structure, which is physically existing and is in compliance with any relevant legislation and the conditions of the Government lease concerned.
  - (c) “New Territories Exempted House” means a domestic building other than a guesthouse or a hotel; or a building primarily used for habitation, other than a guesthouse or a hotel, the ground floor of which may be used as ‘Shop and Services’ or ‘Eating Place’, the building works in respect of which are exempted by a certificate of exemption under Part III of the Buildings Ordinance (Application to the New Territories) Ordinance.

PART B (This Part B applies to land falling within the boundaries of the Plan and the boundaries of “regulated area” as defined in section 1A of the Town Planning Ordinance (hereafter referred to as “Regulated Area”))

- (1) These Notes show the uses or developments on land falling within the boundaries of the Plan which are always permitted and which may be permitted by the Town Planning Board, with or without conditions, on application. Where permission from the Town Planning Board for a use or development is required, the application for such permission should be made in a prescribed form. The application shall be addressed to the Secretary of the Town Planning Board, from whom the prescribed application form may be obtained.
- (2) Any use or development which is always permitted or may be permitted in accordance with these Notes must also conform to any other relevant legislation, the conditions of the Government lease concerned, and any other Government requirements, as may be applicable.
- (3) No action is required to make the use of any land or building within a Regulated Area conform to this Plan, if the use of such land or building was in existence immediately before the first publication in the Gazette of the notice of the South Lantau Coast Outline Zoning Plan (hereafter referred to as ‘the first plan’) and the use has continued since it came into existence. Any material change of such use or any other development (except minor alteration and/or modification to the development of the land or building in respect of such use which is always permitted) must be always permitted in terms of the Plan or in accordance with the permission granted by the Town Planning Board.
- (4) A use or development of any land or building within a Regulated Area which has been permitted under an earlier draft or approved plan for the area and effected or undertaken during the effective period of that plan, is always permitted under this Plan. A use or a change of use relating to an existing building, which was approved under the Buildings Ordinance before the first publication in the Gazette of the notice of the first plan, is always permitted under this Plan. A use or a change of use relating to an existing building, which was approved under the Buildings Ordinance and permitted under a plan or plans prevailing at the time when such use or change of use was approved under the Buildings Ordinance, is also always permitted under this Plan. Any material change of such use or any other development (except minor alteration and/or modification to the completed development of the land or building which is always permitted) must be always permitted in terms of the Plan or in accordance with a permission granted by the Town Planning Board.
- (5) Except to the extent that paragraph (3) or (4) above in this Part B applies, any use or development of any land or building within a Regulated Area, unless always permitted in terms of the Plan, shall not be undertaken or continued, without permission from the Town Planning Board.
- (6) Except as otherwise specified by the Town Planning Board, when a use or material change of use is effected or a development or redevelopment is undertaken, as always permitted in terms of the Plan or in accordance with a permission granted by the Town Planning Board, all permissions granted by the Town Planning Board in respect of the site of the use or material change of use or development or redevelopment shall lapse.

- (7) Road junctions, alignments of roads and boundaries between zones may be subject to minor adjustments as detailed planning proceeds.
- (8) The following uses or developments are always permitted on land falling within the boundaries of the Plan except (a) where the uses or developments are specified in Column 2 of the Notes of individual zones or (b) in areas zoned “Conservation Area” or “Coastal Protection Area”:
- (a) maintenance, repair or demolition of a building;
  - (b) provision, maintenance or repair of plant nursery, amenity planting, open space, rain shelter, refreshment kiosk, footpath, bus stop or lay-by, cycle track, taxi rank, public utility pipeline, electricity mast, lamp pole, telephone booth, telecommunications radio base station, automatic teller machine and shrine;
  - (c) maintenance or repair of road, watercourse, nullah, sewer and drain;
  - (d) geotechnical works, local public works, road works, sewerage works, drainage works, environmental improvement works, marine related facilities and waterworks (excluding works on service reservoir) and such other public works co-ordinated or implemented by Government;
  - (e) rebuilding of New Territories Exempted House;
  - (f) replacement of an existing domestic building, i.e. a domestic building which was in existence on the date of the publication of the first plan, by a New Territories Exempted House; and
  - (g) provision, maintenance or repair of a grave of an indigenous New Territories villager or a locally based fisherman and his family members for which permission has been obtained from Government.
- (9) In areas zoned “Conservation Area” or “Coastal Protection Area”,
- (a) the following uses or developments are always permitted:
    - (i) maintenance or repair of plant nursery, amenity planting, sitting out area, rain shelter, refreshment kiosk, road, watercourse, nullah, public utility pipeline, electricity mast, lamp pole, telephone booth, shrine and grave;
    - (ii) geotechnical works, local public works, road works, sewerage works, drainage works, environmental improvement works, marine related facilities, waterworks (excluding works on service reservoir) and such other public works co-ordinated or implemented by Government; and
    - (iii) provision of amenity planting by Government; and
  - (b) the following uses or developments require permission from the Town Planning Board:  
  
provision of plant nursery, amenity planting (other than by Government), sitting

out area, rain shelter, refreshment kiosk, footpath, public utility pipeline, electricity mast, lamp pole, telephone booth and shrine.

- (10) (a) Except in areas zoned “Conservation Area” or “Coastal Protection Area”, temporary use or development of any land or building not exceeding a period of two months is always permitted provided that no site formation (filling or excavation) is carried out and that the use or development is a use or development specified below:

structures for carnivals, fairs, film shooting on locations, festival celebrations, religious functions or sports events.

- (b) Except as otherwise provided in paragraph (10)(a) in this Part B, and subject to temporary uses for open storage and port back-up purposes which are prohibited in areas zoned “Conservation Area” or “Coastal Protection Area”, temporary use or development of any land or building not exceeding a period of three years requires permission from the Town Planning Board. Notwithstanding that the use or development is not provided for in terms of the Plan, the Town Planning Board may grant permission, with or without conditions, for a maximum period of three years, or refuse to grant permission.
- (c) Temporary use or development of land or building exceeding three years requires permission from the Town Planning Board in accordance with the terms of the Plan.

- (11) Unless otherwise specified, all building, engineering and other operations incidental to and all uses directly related and ancillary to the permitted uses and developments within the same zone are always permitted and no separate permission is required.

- (12) In these Notes,

- (a) unless the context otherwise requires or unless as expressly provided below, terms used in the Notes shall have the meanings as assigned under section 1A of the Town Planning Ordinance
- (b) “existing building” means a building, including a structure, which is physically existing and is in compliance with any relevant legislation and the conditions of the Government lease concerned.
- (c) “New Territories Exempted House” means a domestic building other than a guesthouse or a hotel; or a building primarily used for habitation, other than a guesthouse or a hotel, the ground floor of which may be used as ‘Shop and Services’ or ‘Eating Place’, the building works in respect of which are exempted by a certificate of exemption under Part III of the Buildings Ordinance (Application to the New Territories) Ordinance.

DRAFT SOUTH LANTAU COAST OUTLINE ZONING PLAN NO. S/SLC/22

Schedule of Uses

This Schedule of Uses forms part of the Notes and should be read in conjunction with Part A or Part B of the Notes.

	<u>Page</u>
RESIDENTIAL (GROUP C)	1
VILLAGE TYPE DEVELOPMENT	3
GOVERNMENT, INSTITUTION OR COMMUNITY	5
OPEN SPACE	7
RECREATION	8
OTHER SPECIFIED USES	10
GREEN BELT	11
CONSERVATION AREA	13
COASTAL PROTECTION AREA	15
COUNTRY PARK	18

**RESIDENTIAL (GROUP C)**

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Flat Government Use (Police Reporting Centre, Post Office only) House Utility Installation for Private Project	Ambulance Depot Eating Place Educational Institution Government Refuse Collection Point Government Use (not elsewhere specified) Hotel Institutional Use (not elsewhere specified) Library Petrol Filling Station Place of Recreation, Sports or Culture Private Club Public Clinic Public Convenience Public Transport Terminus or Station Public Utility Installation Public Vehicle Park (excluding container vehicle) Recyclable Collection Centre Religious Institution Residential Institution Rural Committee/Village Office School Shop and Services Social Welfare Facility Training Centre

**Planning Intention**

This zone is intended primarily for low-rise, low-density residential developments where commercial uses serving the residential neighbourhood may be permitted on application to the Town Planning Board.

(Please see next page)

**RESIDENTIAL (GROUP C)** (Cont'd)Remarks

- (a) On land designated “Residential (Group C)”, no new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of a maximum plot ratio of 0.4, a maximum site coverage of 25% and a maximum building height of 2 storeys (7.6m), or the plot ratio, site coverage and height of the existing building, whichever is the greater.
- (b) On land designated “Residential (Group C)1”, no new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of a maximum plot ratio of 0.8, a maximum site coverage of 40% and a maximum building height of 3 storeys (including carport), or the plot ratio, site coverage and height of the existing building, whichever is the greater.
- (c) In determining the maximum plot ratio for the purposes of paragraphs (a) and (b) above, any floor space that is constructed or intended for use solely as car park, loading/unloading bay, plant room and caretaker’s office, or caretaker’s quarters and recreational facilities for the use and benefit of all the owners or occupiers of the domestic building or domestic part of the building, provided such uses and facilities are ancillary and directly related to the development or redevelopment, may be disregarded.
- (d) In determining the maximum site coverage for the purposes of paragraphs (a) and (b) above, any floor space that is constructed or intended for use solely as car park, loading/unloading bay, plant room and caretaker’s office, or caretaker’s quarters and recreational facilities for the use and benefit of all the owners or occupiers of the domestic building or domestic part of the building, shall be included for calculation.
- (e) Based on the individual merits of a development or redevelopment proposal, minor relaxation of the plot ratio/site coverage/building height restrictions stated in paragraphs (a) and (b) above may be considered by Town Planning Board on application under section 16 of the Town Planning Ordinance.

**VILLAGE TYPE DEVELOPMENT**

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Agricultural Use Government Refuse Collection Point Government Use (Police Reporting Centre, Post Office only) House (New Territories Exempted House only) On-Farm Domestic Structure Public Convenience Public Vehicle Park (for cycles only) Religious Institution (Ancestral Hall only) Rural Committee/Village Office	Burial Ground Eating Place Field Study/Education/Visitor Centre Government Use (not elsewhere specified) # Hotel (Holiday House only) House (not elsewhere specified) Institutional Use (not elsewhere specified) # Petrol Filling Station Pier Place of Recreation, Sports or Culture Private Club Public Clinic Public Transport Terminus or Station Public Utility Installation # Public Vehicle Park (not elsewhere specified, excluding container vehicle) Religious Institution (not elsewhere specified) # Residential Institution # School # Shop and Services Social Welfare Facility # Utility Installation for Private Project

In addition, the following uses are always permitted on the ground floor of a New Territories Exempted House:

Eating Place  
 Library  
 School  
 Shop and Services

(Please see next page)

**VILLAGE TYPE DEVELOPMENT** (Cont'd)Planning Intention

The planning intention of this zone is to designate both existing recognized villages and areas of land considered suitable for village expansion. Land within this zone is primarily intended for development of Small Houses by indigenous villagers. It is also intended to concentrate village type development within this zone for a more orderly development pattern, efficient use of land and provision of infrastructures and services. Selected commercial and community uses serving the needs of the villagers and in support of the village development are always permitted on the ground floor of a New Territories Exempted House. Other commercial, community and recreational uses may be permitted on application to the Town Planning Board.

Remarks

- (a) No new development, or addition, alteration and/or modification to or redevelopment of an existing building (except development or redevelopment to those annotated with #) shall result in a total development and/or redevelopment in excess of a maximum building height of 3 storeys (8.23m) or the height of the existing building, whichever is the greater.
- (b) Based on the individual merits of a development or redevelopment proposal, minor relaxation of the building height restriction stated in paragraph (a) above may be considered by Town Planning Board on application under section 16 of the Town Planning Ordinance.

**GOVERNMENT, INSTITUTION OR COMMUNITY**

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Ambulance Depot Animal Quarantine Centre (in Government building only) Broadcasting, Television and/or Film Studio Correctional Institution Eating Place (Canteen, Cooked Food Centre only) Educational Institution Exhibition or Convention Hall Field Study/Education/Visitor Centre Government Refuse Collection Point Government Use (not elsewhere specified) Hospital Institutional Use (not elsewhere specified) Library Market Pier Place of Recreation, Sports or Culture Public Clinic Public Convenience Public Transport Terminus or Station Public Utility Installation Public Vehicle Park (excluding container vehicle) Recyclable Collection Centre Religious Institution Research, Design and Development Centre Rural Committee/Village Office School Service Reservoir Social Welfare Facility Training Centre Wholesale Trade	Animal Boarding Establishment Animal Quarantine Centre (not elsewhere specified) Columbarium Crematorium Eating Place (not elsewhere specified) Flat Funeral Facility Helicopter Landing Pad Holiday Camp Hotel House (other than rebuilding of New Territories Exempted House or replacement of existing domestic building by New Territories Exempted House permitted under the covering Notes) Marine Fuelling Station Off-course Betting Centre Office Petrol Filling Station Place of Entertainment Private Club Radar, Telecommunications Electronic Microwave Repeater, Television and/or Radio Transmitter Installation Refuse Disposal Installation (Refuse Transfer Station only) Residential Institution Sewage Treatment/Screening Plant Shop and Services (not elsewhere specified) Utility Installation for Private Project Zoo

(Please see next page)

**GOVERNMENT, INSTITUTION OR COMMUNITY** (Cont'd)

Planning Intention

This zone is intended primarily for the provision of Government, institution or community facilities serving the needs of the local residents and/or a wider district, region or the territory. It is also intended to provide land for uses directly related to or in support of the work of the Government, organizations providing social services to meet community needs, and other institutional establishments.

**OPEN SPACE**


---

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Aviary	Eating Place
Barbecue Spot	Government Refuse Collection Point
Bathing Beach	Government Use (not elsewhere specified)
Field Study/Education/Visitor Centre	Holiday Camp
Park and Garden	Place of Entertainment
Pavilion	Place of Recreation, Sports or Culture
Pedestrian Area	Private Club
Picnic Area	Public Transport Terminus or Station
Playground/Playing Field	Public Utility Installation
Promenade	Public Vehicle Park
Public Convenience	(excluding container vehicle)
Sitting Out Area	Religious Institution
Zoo	Service Reservoir
	Shop and Services
	Tent Camping Ground
	Utility Installation for Private Project

---

**Planning Intention**

This zone is intended primarily for the provision of outdoor open-air public space for active and/or passive recreational uses serving the needs of local residents as well as the general public.

**RECREATION**

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Agricultural Use Barbecue Spot Field Study/Education/Visitor Centre Government Use (Police Reporting Centre only) Holiday Camp On-Farm Domestic Structure Picnic Area Place of Recreation, Sports or Culture Public Convenience Rural Committee/Village Office Tent Camping Ground	Animal Boarding Establishment Broadcasting, Television and/or Film Studio Eating Place Flat Golf Course Government Refuse Collection Point Government Use (not elsewhere specified) Hotel House (other than rebuilding of New Territories Exempted House or replacement of existing domestic building by New Territories Exempted House permitted under the covering Notes) Place of Entertainment Private Club Public Utility Installation Public Vehicle Park (excluding container vehicle) Religious Institution Residential Institution Shop and Services Theme Park Utility Installation for Private Project Zoo

**Planning Intention**

This zone is intended primarily for recreational developments for the use of the general public. It encourages the development of active and/or passive recreation and tourism/eco-tourism. Uses in support of the recreational developments may be permitted subject to planning permission.

(Please see next page)

**RECREATION** (Cont'd)

Remarks

- (a) No new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of a maximum building height of 3 storeys, or the height of the building which was in existence on the date of the first publication in the Gazette of the notice of the draft South Lantau Coast Outline Zoning Plan No. S/SLC/22, whichever is the greater.
- (b) No residential development shall result in a total development in excess of a maximum plot ratio of 0.2 and a maximum building height of 2 storeys (6m).
- (c) In determining the maximum plot ratio for the purposes of paragraph (b) above, any floor space that is constructed or intended for use solely as plant room, caretaker's office and caretaker's quarters, provided such uses and facilities are ancillary and directly related to the development or redevelopment, may be disregarded.
- (d) Based on the individual merits of a development or redevelopment proposal, minor relaxation of the plot ratio and building height restrictions stated in paragraphs (a) and (b) above may be considered by the Town Planning Board on application under section 16 of the Town Planning Ordinance.

**OTHER SPECIFIED USES**


---

Column 1  
Uses always permitted

Column 2  
Uses that may be permitted with or  
without conditions on application  
to the Town Planning Board

---

**For “Sewage Treatment Works” Only**

Sewage Treatment Works

Government Use (not elsewhere specified)  
Public Utility Installation**Planning Intention**

This zone is intended to designate land for sewage treatment works.

**For “Waterworks Pumping Station” Only**

Water Pumping Station

Government Use  
Public Utility Installation (not elsewhere  
specified)**Planning Intention**

This zone is intended to designate land for the purpose of a water pumping station in connection with the water supply system serving Lantau and the western part of Hong Kong Island.

**For “Water Treatment Works” Only**Water Treatment Works  
Service ReservoirGovernment Use (not elsewhere specified)  
Public Utility Installation**Planning Intention**

This zone is intended primarily for the provision of water treatment works serving the needs of the community.

**GREEN BELT**

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Agricultural Use Barbecue Spot Country Park* Government Use (Police Reporting Centre only) Nature Reserve Nature Trail On-Farm Domestic Structure Picnic Area Public Convenience Public Vehicle Park (for cycles only) Tent Camping Ground Wild Animals Protection Area	Animal Boarding Establishment Broadcasting, Television and/or Film Studio Burial Ground Columbarium (within a Religious Institution or extension of existing Columbarium only) Crematorium (within a Religious Institution or extension of existing Crematorium only) Field Study/Education/Visitor Centre Flat Golf Course Government Refuse Collection Point Government Use (not elsewhere specified) Helicopter Landing Pad Holiday Camp House (other than rebuilding of New Territories Exempted House or replacement of existing domestic building by New Territories Exempted House permitted under the covering Notes) Marine Fuelling Station Petrol Filling Station Pier Place of Recreation, Sports or Culture Public Transport Terminus or Station Public Utility Installation Public Vehicle Park (not elsewhere specified, excluding container vehicle) Radar, Telecommunications Electronic Microwave Repeater, Television and/or Radio Transmitter Installation Religious Institution Residential Institution Rural Committee/Village Office School Service Reservoir Social Welfare Facility Utility Installation for Private Project Zoo

(Please see next page)

**GREEN BELT** (Cont'd)

- \* Country Park means a country park or special area as designated under the Country Parks Ordinance (Cap. 208). All uses and developments require consent from the Country and Marine Parks Authority and approval from the Town Planning Board is not required.

**Planning Intention**

The planning intention of this zone is primarily for defining the limits of urban and sub-urban development areas by natural features and to contain urban sprawl as well as to provide passive recreational outlets. There is a general presumption against development within this zone.

**Remarks**

- (a) On land previously falling within the "Green Belt" zone on the South Lantau Coast Outline Zoning Plan No. S/SLC/21, any diversion of stream, including that to effect a change of use to any of those specified in Columns 1 and 2 above or the uses or developments always permitted under the covering Notes (except public works co-ordinated or implemented by Government, and maintenance, repair or rebuilding works), shall not be undertaken or continued on or after the date of the publication in the Gazette of the notice of the draft South Lantau Coast Outline Zoning Plan No. S/SLC/13 without the permission from the Town Planning Board under section 16 of the Town Planning Ordinance.
- (b) On land previously falling within the "Green Belt" zone on the South Lantau Coast Outline Zoning Plan No. S/SLC/21, any filling of land/pond or excavation of land, including that to effect a change of use to any of those specified in Columns 1 and 2 above or the uses or developments always permitted under the covering Notes (except public works co-ordinated or implemented by Government, and maintenance, repair or rebuilding works), shall not be undertaken or continued on or after the date of the publication in the Gazette of the notice of the draft South Lantau Coast Outline Zoning Plan No. S/SLC/22 without the permission from the Town Planning Board under section 16 of the Town Planning Ordinance.
- (c) On land not previously falling within the "Green Belt" zone on the South Lantau Coast Outline Zoning Plan No. S/SLC/21, any diversion of stream, filling of land/pond or excavation of land, including that to effect a change of use to any of those specified in Columns 1 and 2 above or the uses or developments always permitted under the covering Notes (except public works co-ordinated or implemented by Government, and maintenance, repair or rebuilding works), shall not be undertaken or continued on or after the date of the publication in the Gazette of the notice of the draft South Lantau Coast Outline Zoning Plan No. S/SLC/22 without the permission from the Town Planning Board under section 16 of the Town Planning Ordinance.

**CONSERVATION AREA**

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Agricultural Use (other than Plant Nursery) Country Park* Nature Reserve Nature Trail On-Farm Domestic Structure Picnic Area Wetland Habitat Wild Animals Protection Area	Barbecue Spot Field Study/Education/Visitor Centre Government Refuse Collection Point Government Use (not elsewhere specified) Holiday Camp House (Redevelopment only) Pier Public Convenience Public Utility Installation Radar, Telecommunications Electronic Microwave Repeater, Television and/or Radar Transmitter Installation Tent Camping Ground Utility Installation for Private Project

\* Country Park means a country park or special area as designated under the Country Parks Ordinance (Cap. 208). All uses and developments require consent from the Country and Marine Parks Authority and approval from the Town Planning Board is not required.

**Planning Intention**

This zoning is intended to protect and retain the existing natural landscape, ecological and topographical features of the area for conservation, educational and research purposes and to separate sensitive natural environment such as Country Park from the adverse effects of development. In particular, it is intended to conserve the ecological values of the wetland habitats which form an integral part of the wetland ecosystem.

There is a general presumption against development in this zone. In general, only developments that are needed to support the conservation of the existing natural landscape habitats or scenic quality of the area or are essential infrastructure projects with overriding public interest may be permitted.

(Please see next page)

**CONSERVATION AREA** (Cont'd)Remarks

- (a) No redevelopment, including alteration and/or modification, of an existing house shall result in a total redevelopment in excess of a maximum plot ratio of 0.4, a maximum site coverage of 25% and a maximum building height of 2 storeys (7.6m), or the plot ratio, site coverage and height of the house, whichever is the greater.
- (b) In determining the maximum plot ratio for the purposes of paragraph (a) above, any floor space that is constructed or intended for use solely as car park, loading/unloading bay, plant room and caretaker's office, or caretaker's quarters and recreational facilities for the use and benefit of all the owners or occupiers of the domestic building or domestic part of the building, provided such uses and facilities are ancillary and directly related to the development or redevelopment, may be disregarded.
- (c) In determining the maximum site coverage for the purposes of paragraph (a) above, any floor space that is constructed or intended for use solely as car park, loading/unloading bay, plant room and caretaker's office, or caretaker's quarters and recreational facilities for the use and benefit of all the owners or occupiers of the domestic building or domestic part of the building, shall be included for calculation.
- (d) Based on the individual merits of a redevelopment proposal, minor relaxation of the plot ratio/site coverage/building height restrictions stated in paragraph (a) above may be considered by Town Planning Board on application under section 16 of the Town Planning Ordinance.
- (e) Any diversion of stream, filling of land/pond or excavation of land, including that to effect a change of use to any of those specified in Columns 1 and 2 above or the uses or developments always permitted under the covering Notes (except public works co-ordinated or implemented by Government, maintenance or repair works) shall not be undertaken or continued on or after the date of the publication in the Gazette of the notice of the draft South Lantau Coast Outline Zoning Plan No. S/SLC/22 without the permission from the Town Planning Board under section 16 of the Town Planning Ordinance.

**COASTAL PROTECTION AREA**

Column 1 Uses always permitted	Column 2 Uses that may be permitted with or without conditions on application to the Town Planning Board
Agricultural Use (other than Plant Nursery) Barbecue Spot Bathing Beach Country Park* Nature Reserve Nature Trail On-Farm Domestic Structure Picnic Area Wetland Habitat Wild Animals Protection Area	Field Study/Education/Visitor Centre Government Use Holiday Camp House (Redevelopment only) Pier Public Convenience Public Utility Installation Radar, Telecommunications Electronic Microwave Repeater, Television and/or Radar Transmitter Installation Tent Camping Ground Utility Installation for Private Project

\* Country Park means a country park or special area as designated under the Country Parks Ordinance (Cap. 208). All uses and developments require consent from the Country and Marine Parks Authority and approval from the Town Planning Board is not required.

**Planning Intention**

This zoning is intended to conserve, protect and retain the natural coastlines and the sensitive coastal natural environment, including attractive geological features, physical landform or area of high landscape, scenic or ecological value, with a minimum of built development. It may also cover areas which serve as natural protection areas sheltering nearby developments against the effects of coastal erosion. It is also intended to safeguard the beaches and their immediate hinterland and to prevent haphazard ribbon development along the South Lantau Coast.

There is a general presumption against development in this zone. In general, only developments that are needed to support the conservation of the existing natural landscape or scenic quality of the area or are essential infrastructure projects with overriding public interest may be permitted.

(Please see next page)

**COASTAL PROTECTION AREA** (Cont'd)Remarks

- (a) No redevelopment, including alteration and/or modification, of an existing house shall result in a total redevelopment in excess of a maximum plot ratio of 0.4, a maximum site coverage of 25% and a maximum building height of 2 storeys (7.6m), or the plot ratio, site coverage and height of the existing house, whichever is the greater.
- (b) In determining the maximum plot ratio for the purposes of paragraph (a) above, any floor space that is constructed or intended for use solely as car park, loading/unloading bay, plant room and caretaker's office, or caretaker's quarters and recreational facilities for the use and benefit of all the owners or occupiers of the domestic building or domestic part of the building, provided such uses and facilities are ancillary and directly related to the development or redevelopment, may be disregarded.
- (c) In determining the maximum site coverage for the purposes of paragraph (a) above, any floor space that is constructed or intended for use solely as car park, loading/unloading bay, plant room and caretaker's office, or caretaker's quarters and recreational facilities for the use and benefit of all the owners or occupiers of the domestic building or domestic part of the building, shall be included for calculation.
- (d) Based on the individual merits of a redevelopment proposal, minor relaxation of the plot ratio/site coverage/building height restrictions stated in paragraph (a) above may be considered by Town Planning Board on application under section 16 of the Town Planning Ordinance.
- (e) On land previously falling within the "Coastal Protection Area" zone on the South Lantau Coast Outline Zoning Plan No. S/SLC/21, any diversion of stream, filling of land or excavation of land, including that to effect a change of use to any of those specified in Columns 1 and 2 above or the uses or developments always permitted under the covering Notes (except public works co-ordinated or implemented by Government, and maintenance or repair works), shall not be undertaken or continued on or after the date of the publication in the Gazette of the notice of the draft South Lantau Coast Outline Zoning Plan No. S/SLC/13 without the permission from the Town Planning Board under section 16 of the Town Planning Ordinance.

(Please see next page)

**COASTAL PROTECTION AREA** (Cont'd)Remarks (cont'd)

- (f) On land previously falling within the “Coastal Protection Area” zone on the South Lantau Coast Outline Zoning Plan No. S/SLC/21, any filling of pond, including that to effect a change of use to any of those specified in Columns 1 and 2 above or the uses or developments always permitted under the covering Notes (except public works co-ordinated or implemented by Government, and maintenance or repair works), shall not be undertaken or continued on or after the date of the publication in the Gazette of the notice of the draft South Lantau Coast Outline Zoning Plan No. S/SLC/22 without the permission from the Town Planning Board under section 16 of the Town Planning Ordinance.
- (g) On land not previously falling within the “Coastal Protection Area” zone on the South Lantau Coast Outline Zoning Plan No. S/SLC/21, any diversion of stream, filling of land/pond or excavation of land, including that to effect a change of use to any of those specified in Columns 1 and 2 above or the uses or developments always permitted under the covering Notes (except public works co-ordinated or implemented by Government, and maintenance or repair works), shall not be undertaken or continued on or after the date of the publication in the Gazette of the notice of the draft South Lantau Coast Outline Zoning Plan No. S/SLC/22 without the permission from the Town Planning Board under section 16 of the Town Planning Ordinance.

**COUNTRY PARK**

Country Park means a country park or special area as designated under the Country Parks Ordinance (Cap. 208). All uses and developments require consent from the Country and Marine Parks Authority and approval from the Town Planning Board is not required.

**DRAFT SOUTH LANTAU COAST OUTLINE ZONING PLAN NO. S/SLC/22**

**EXPLANATORY STATEMENT**

DRAFT SOUTH LANTAU COAST OUTLINE ZONING PLAN NO. S/SLC/22

EXPLANATORY STATEMENT

<u>Contents</u>	<u>Page</u>
1. INTRODUCTION	1
2. AUTHORITY FOR THE PLAN AND PROCEDURE	1
3. OBJECT OF THE PLAN	3
4. NOTES OF THE PLAN	3
5. THE PLANNING SCHEME AREA	4
6. POPULATION	5
7. LAND USE ZONINGS	
7.1 Residential (Group C)	5
7.2 Village Type Development	5
7.3 Government, Institution or Community	6
7.4 Open Space	6
7.5 Recreation	7
7.6 Other Specified Uses	7
7.7 Green Belt	8
7.8 Conservation Area	9
7.9 Coastal Protection Area	9
7.10 Country Park	10
8. COMMUNICATIONS	10
9. UTILITY SERVICES	11
10. CULTURAL HERITAGE	12
11. IMPLEMENTATION	13
12. PLANNING CONTROL	13

# **DRAFT SOUTH LANTAU COAST OUTLINE ZONING PLAN NO. S/SLC/22**

(Being a Draft Plan for the Purposes of the Town Planning Ordinance)

## **EXPLANATORY STATEMENT**

Note : For the purposes of the Town Planning Ordinance, this statement shall not be deemed to constitute a part of the Plan.

### **1. INTRODUCTION**

This Explanatory Statement is intended to assist an understanding of the draft South Lantau Coast Outline Zoning Plan (OZP) No. S/SLC/22. It reflects the planning intention and objectives of the Town Planning Board (the Board) for various land use zonings of the Plan.

### **2. AUTHORITY FOR THE PLAN AND PROCEDURE**

- 2.1 Under the power delegated by the then Governor, the then Secretary for Planning, Environment and Lands directed the Board in June 1972, under section 3 of the Town Planning Ordinance (the Ordinance), to prepare a statutory plan for the main coastal strip of South Lantau. The draft South Lantau Coast OZP No. LLT/18 was prepared and exhibited for public inspection under section 5 of the Ordinance on 30 May 1980. The OZP was subsequently amended twice and exhibited for public inspection under section 6(7) and/or 7 of the Ordinance.
- 2.2 On 13 December 1994, the then Governor in Council under section 9(1)(c) of the Ordinance, referred the draft OZP No. S/SLC/4 to the Board for further amendment. The OZP was subsequently amended twice and exhibited for public inspection under section 5 or 7 of the Ordinance.
- 2.3 On 20 April 1999, the Chief Executive in Council (CE in C), under section 9(1)(a) of the Ordinance, approved the draft OZP, which was subsequently renumbered as S/SLC/7. On 30 November 1999, the CE in C referred the approved OZP No. S/SLC/7 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. The OZP was subsequently amended and exhibited for public inspection under section 12(3) of the Ordinance.
- 2.4 On 21 November 2000, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft OZP, which was subsequently renumbered as S/SLC/9. On 10 April 2001, the CE in C referred the approved OZP No. S/SLC/9 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. The OZP was subsequently amended twice and exhibited for public inspection under section 5 or 7 of the Ordinance.

- 2.5 On 28 May 2002, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft OZP, which was subsequently renumbered as S/SLC/12. On 9 December 2003, the CE in C referred the approved OZP No. S/SLC/12 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance.
- 2.6 On 26 March 2004, the draft OZP No. S/SLC/13, incorporating amendments to the Notes to reflect the revised Master Schedule of Notes to Statutory Plans endorsed by the Board, was exhibited for public inspection under section 5 of the Ordinance. On 1 February 2005, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft OZP, which was subsequently renumbered as S/SLC/14.
- 2.7 On 30 June 2009, the CE in C referred the approved OZP No. S/SLC/14 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. On 27 November 2009, the draft OZP No. S/SLC/15 was exhibited for public inspection under section 5 of the Ordinance. On 2 November 2010, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft OZP, which was subsequently renumbered as S/SLC/16.
- 2.8 On 5 June 2012, the CE in C referred the approved OZP No. S/SLC/16 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. Since then, the OZP has been amended twice and exhibited for public inspection under section 5 and section 7 of the Ordinance.
- 2.9 On 2 September 2014, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft OZP, which was renumbered as S/SLC/19. On 19 September 2014, the approved OZP No. S/SLC/19 was exhibited for public inspection under Section 9(5) of the Ordinance.
- 2.10 On 14 March 2017, the CE in C referred the approved OZP No. S/SLC/19 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. The reference of the OZP was notified in the Gazette on 24 March 2017 under section 12(2) of the Ordinance.
- 2.11 On 2 June 2017, the draft OZP No. S/SLC/20, incorporating mainly the amendment to rezone a site at Pui O from “Coastal Protection Area” to “Other Specified Uses” annotated “Sewage Treatment Works”, was exhibited for public inspection under section 5 of the Ordinance. No valid representation was received.
- 2.12 On 9 January 2018, the CE in C, under section 9(1)(a) of the Ordinance, approved the draft South Lantau Coast OZP, which was subsequently renumbered as S/SLC/21. On 19 January 2018, the approved South Lantau Coast OZP No. S/SLC/21 was exhibited for public inspection under section 9(5) of the Ordinance.
- 2.13 On 27 June 2023, the CE in C referred the approved OZP No. S/SLC/21 to the Board for amendment under section 12(1)(b)(ii) of the Ordinance. The reference back was notified in the Gazette on 7 July 2023 under section 12(2) of the Ordinance.

- 2.14 On 26 July 2023, the Secretary for Development under the delegated authority of Chief Executive directed the Board under Section 3(1)(a) of the Ordinance to extend the planning scheme boundary of the South Lantau Coast OZP to include an area not covered by the OZP nor the Lantau South Country Park.
- 2.15 On 15 September 2023, the draft OZP No. S/SLC/22 (the Plan), incorporating mainly the amendments based on the findings of land use review, was exhibited for public inspection under section 5 of the Ordinance. On the same day, the Secretary for Development, under section 21A(3) of the Ordinance, notified in the Gazette the designation of South Lantau Coast Regulated Area (hereafter referred to as “Regulated Area”). The boundary of the Regulated Area is shown on Plan No. RA/SLC/1.

### **3. OBJECT OF THE PLAN**

- 3.1 The object of the Plan is to indicate the broad land use zonings and major road network so that development and redevelopment of land within the Planning Scheme Area can be put under statutory planning control. It also provides the planning framework for preparing more detailed non-statutory plans which form the basis for public works planning and allocation of sites for various uses.
- 3.2 The Plan is to illustrate only the broad principles of development and to provide guidance for more detailed planning. It is a small-scale plan, the road alignments and boundaries between the land use zones may be subject to minor adjustments as detailed planning and development proceed.
- 3.3 Since the Plan is to show broad land use zonings, there would be situations in which small strips of land not intended for building development purposes and carry no development right under the lease, such as the areas restricted as non-building area or for garden, slope maintenance and access road purposes, are included in the residential zones. The general principle is that such areas should not be taken into account in plot ratio and site coverage calculations. Development within residential zones should be restricted to building lots carrying development right in order to maintain the character and amenity of the area and not to overload the road network in this area.

### **4. NOTES OF THE PLAN**

- 4.1 Attached to the Plan is a set of Notes which shows the types of uses or developments which are always permitted within the Planning Scheme Area and in a particular zone and which may be permitted by the Board, with or without conditions, on application. The provision for application for planning permission under section 16 of the Ordinance allows greater flexibility in land use planning and control of development to meet changing needs. To provide flexibility for development with design adapted to the characteristics of particular sites, minor relaxation of the specific development restriction(s) stated in the Notes for particular zones may be considered by the Board through the planning permission system. Each proposal will be considered on its individual planning merits.

- 4.2 For the guidance of the general public, a set of definitions that explains some of the terms used in the Notes may be obtained from the Technical Services Division of the Planning Department (PlanD) and can be downloaded from the Board's website at <http://www.tpb.gov.hk>.

## **5. THE PLANNING SCHEME AREA**

- 5.1 The Planning Scheme Area (the Area) covers a total of about 2,456 ha of land along the South Lantau Coast. In the north, it is almost all bounded by the Lantau South Country Park and in the south by the existing coastlines. Some parts of the Country Park also fall within the Area.
- 5.2 The Area comprises extensive densely vegetated hillslopes forming a scenic natural backdrop for the villages and low-rise, low-density residential developments scattered along the foothills. The dominant coastal topographical features are the two hilly peninsulas, namely Chi Ma Wan Peninsula and the peninsula at Lo Kei Wan, and the coastal strip in-between embracing a number of beaches, wetland and mangrove areas. The gazetted public beaches include Pui O Beach, Upper Cheung Sha Beach, Lower Cheung Sha Beach and Tong Fuk Beach. The area to the west of Lo Kei Wan is much more hilly with numerous small beaches. Small areas near Shek Pik Peninsula, Chi Ma Wan Peninsula and the peninsulas at Lo Kei Wan and Fan Lau are within the Lantau South Country Park and heavily wooded. Pockets of woodland and coastal lowland are also found along the coast and to the north of South Lantau Road. In order to conserve the rural character and the natural landscape resources and habitats of the Area, excavation or filling of land, diversion of stream and large-scale developments should be discouraged.
- 5.3 The existing population concentrates mainly at several recognised villages including San Shek Wan Tsuen, Pui O San Wai Tsuen, Pui O Lo Wai Tsuen, Lo Uk Tsuen, Ham Tin Tsuen, Cheung Sha Sheung Tsuen, Cheung Sha Ha Tsuen, Tong Fuk Tsuen and Shui Hau Tsuen and the low-rise, low-density residential developments at Cheung Sha.
- 5.4 The Sustainable Lantau Blueprint (the Blueprint), which was promulgated in 2017, embraces the overarching principle of "Development in the North; Conservation for the South". The predominant part of Lantau, in particular South Lantau, would be conserved for its natural and cultural resources and where appropriate, low-impact leisure and recreational uses would be developed for public enjoyment. The leisure and recreational proposals should be environmentally sustainable and be compatible with the local context. In 2020, the Lantau Conservation and Recreation Masterplan was formulated based on the Blueprint and promulgated to provide a framework guiding the conservation and recreation initiatives in South Lantau.
- 5.5 The Area is environmentally and ecologically sensitive and comprises a wide diversity of natural habitats such as woodland, shrubland, grassland, streamcourses, agricultural land and sandy shore, which form an integral part of the natural environment extended from the woodland system in the adjoining Lantau South Country Park. There are also two Ecologically Important Streams in Pui O and Tong Fuk flowing downhill towards to Pui O Wan and the

area to the east of Tong Fuk Miu Wan respectively. Nevertheless, there are haphazard and uncontrolled developments involving dumping of construction materials as well as excavation and land filling activities that may adversely affect the rural and natural character of the Area. To better protect the natural and landscape character of the Area to avoid disturbance to the natural environment, an area of about 626 ha has been designated as Regulated Area (Plan No. RA/SLC/1) to enable the Planning Authority to instigate enforcement actions against any unauthorized developments. A “two-part” covering Notes system is introduced to accommodate the different provisions for (i) land falling within the boundaries of the OZP which are not within the boundaries of the Regulated Area (i.e. “Part A”) and (ii) land falling within the boundaries of the OZP and boundaries of the Regulated Area (i.e. “Part B”).

## **6. POPULATION**

Based on the 2021 Population Census, the population of the Area as estimated by PlanD was about 5,900 persons. It is estimated that the planned population in the Area would be about 8,000 persons. During weekends and public holidays, there are many visitors to the Area.

## **7. LAND USE ZONINGS**

### **7.1 Residential (Group C) (“R(C)”) : Total Area 55.74 ha**

7.1.1 The planning intention of this zone is primarily for low-rise and low-density residential developments. Nine “R(C)” zones are designated on the Plan. Two are located at the southern tip of Chi Ma Wan Peninsula, which mainly rely on marine access. Six are located along South Lantau Road between Cheung Sha and Pui O. The remaining one is located at Shui Hau.

7.1.2 No development or redevelopment within the “R(C)” zones should exceed a maximum plot ratio of 0.4, a maximum site coverage of 25% and a maximum building height of 2 storeys (7.6m), or the plot ratio, site coverage and height of the existing building, whichever is the greater. These restrictions are primarily to reflect the existing and committed development intensities so as to maintain the existing rural and natural character of the South Lantau Coast and to avoid overtaxing the limited road capacity and infrastructure in the area.

7.1.3 A site at Cheung Sha is zoned “R(C)1”. No development or redevelopment within the “R(C)1” sub-area should exceed a maximum plot ratio of 0.8, a maximum site coverage of 40% and a maximum building height of 3 storeys (including carport), or the plot ratio, site coverage and height of the existing building, whichever is the greater.

### **7.2 Village Type Development (“V”) : Total Area 85.83 ha**

7.2.1 The planning intention of this zone is to designate both existing recognised villages and areas of land considered suitable for village

expansion. Land within the “V” zones is primarily intended for development of Small Houses by indigenous villagers. It is also intended to concentrate village type development within the “V” zones for a more orderly development pattern, efficient use of land and provision of infrastructures and services. Selected commercial and community uses serving the needs of the villagers and in support of the village development are always permitted on the ground floor of a New Territories Exempted House. Other commercial, community and recreational uses may be permitted on application to the Board on the basis that these uses would meet the needs of villagers and would not adversely affect the character of these villages.

7.2.2 On land designated “V”, any new building or any addition, alteration and/or modification to or redevelopment of the existing building should not result in a total development and/or redevelopment in excess of a maximum building height of 3 storeys (8.23m) or the height of the existing building, whichever is the greater.

7.2.3 The existing recognised villages at Mong Tung Wan, Tai Long, Shap Long, Ham Tin, Pui O, Lo Uk, San Shek Wan, Cheung Sha, Tong Fuk, Shui Hau, Tai Long Wan and Fan Lau are zoned “V”. The boundaries of the “V” zones are drawn up having regard to the village ‘environs’, Small House demand, topography and site constraints. Areas of difficult terrain, dense vegetation, streamcourses and burial grounds have been avoided.

7.3 Government, Institution or Community (“G/IC”) : Total Area 90.10 ha

The planning intention of this zone is primarily for the provision of Government, institution and community (GIC) facilities serving the needs of the local residents and/or a wider district, region or the territory. It is also intended to provide land for uses directly related to or in support of the work of the Government, organizations providing social services to meet community needs, and other institutional establishments. The major existing GIC facilities include Tong Fuk Correctional Institution, Shek Pik Prison, Sha Tsui Correctional Institution, Bui O Public School, Hung Shing Temple at Tong Fuk Miu Wan, electric substations at Cheung Sha and Tong Fuk, and a special school at Tung Wan.

7.4 Open Space (“O”) : Total Area 0.58 ha

7.4.1 The planning intention of this zone is primarily for the provision of outdoor open-air public space for active and/or passive recreational uses serving the needs of local residents as well as the general public.

7.4.2 This zone covers the open space facilities managed by the Leisure and Cultural Services Department, such as Pui O Children’s Playground, Pui O Playground, Cheung Sha Ha Tsuen Basketball Court and Cheung Sha Ha Tsuen Children’s Playground.

7.5 Recreation (“REC”) : Total Area 6.38 ha

- 7.5.1 The planning intention of this zone is primarily for recreational developments for the use of the general public. It encourages the development of active and/or passive recreation and tourism/eco-tourism. Uses in support of the recreational developments may be permitted subject to planning permission.
- 7.5.2 There are two “REC” zones being designated on the Plan to promote recreational development. It mainly covers Victoria Resort and a stretch of land in Pui O abutting South Lantau Road and Chi Ma Wan Road which are currently vacant or occupied by open storage and workshops, as well as the former site of ex-Hong Kong Youth Hostels Association Jockey Club Mong Tung Wan Hostel in Mong Tung Wan.
- 7.5.3 No new development, or addition, alteration and/or modification to or redevelopment of an existing building shall result in a total development and/or redevelopment in excess of a maximum building height of 3 storeys, or the height of the building which was in existence on the date of the first publication in the Gazette of the notice of the draft South Lantau Coast Outline Zoning Plan No. S/SLC/22, whichever is the greater.
- 7.5.4 Residential development will generally not be allowed in this zone except where it can be established that such use, in the form of holiday accommodation, is ancillary to and in support of the recreational uses. No residential development shall result in a total development in excess of a maximum plot ratio of 0.2 and a maximum building height of 2 storeys (6m).
- 7.5.5 To provide flexibility for innovative design adapted to the characteristics of particular sites, minor relaxation of the building height and plot ratio restrictions may be considered by the Board through the planning permission system. Each proposal will be considered on its individual planning merits.
- 7.5.6 The plot ratio under “REC” zone is regarded as being stipulated in an amended statutory plan according to the Joint Practice Note No. 4 “Development Control Parameters Plot Ratio/Gross Floor Area”, and shall be subject to the streamlining arrangements stated therein.

7.6 Other Specified Uses (“OU”) : Total Area 2.66 ha

7.6.1 Sewage Treatment Works

A site at Pui O to the south of South Lantau Road is zoned “OU” annotated “Sewage Treatment Works”. This zone is intended to designate land for sewage treatment works.

7.6.2 Waterworks Pumping Station

Two sites off the eastern boundary of Pui O Lo Wai Tsuen and abutting

South Lantau Road are zoned “OU” annotated “Waterworks Pumping Station”. This zone is intended to designate land for the purpose of two water pumping stations in connection with the water supply system serving Lantau and the western part of Hong Kong Island.

### 7.6.3 Water Treatment Works

A site to the north of Cheung Sha is zoned “OU” annotated “Water Treatment Works”. This zone is intended to designate land for the purpose of a water treatment works serving the needs of the community.

## 7.7 Green Belt (“GB”) : Total Area 472.22 ha

7.7.1 The planning intention of this zone is primarily to define the limits of development areas, to preserve existing well-wooded hillslopes and other natural features, as well as to provide passive recreational outlets for the local population and visitors. It mainly covers the extensive well-vegetated uplands and hillsides, spurs and stream valleys, coastal pockets of land and isolated knolls adjoining the Lantau South Country Park.

7.7.2 Most of the northern part of the Area comprises steep slopes which are unsuitable for development. These areas, however, provide an important buffer for the Lantau South Country Park and a good landscape setting for the scattered “R(C)” zones and village type developments along the coast and are zoned “GB”. These hillslopes also embrace a number of natural streamcourses irrigating the agricultural land and the coastal wetland and should be protected from filling, excavation or stream diversion. Pockets of agricultural land at Chi Ma Wan Peninsula near the Lantau South Country Park are also zoned “GB”.

7.7.3 There is a general presumption against development within the “GB” zone. Development within this zone will be strictly controlled. Any building development will require permission from the Board and development proposals will be considered by the Board on individual merits, taking into account the relevant Town Planning Board Guidelines. As diversion of stream, filling of land/pond or excavation of land may cause adverse drainage and environmental impacts on the adjacent areas and the natural environment, permission from the Board is required for such works and related activities except public works co-ordinated or implemented by Government, and maintenance, repair or rebuilding works. Low impact, environmentally sustainable and compatible low-rise leisure and recreation uses and facilities for eco-tourism like camping/glamping sites, eco-lodge, eating place, visitor/education centre, and for adventure park, etc. with appropriate supporting facilities which have proved to have no adverse impacts on environmental and other relevant aspects could be favourably considered.

7.8 Conservation Area (“CA”) : Total Area 60.65 ha

- 7.8.1 This zone is intended to protect and retain the existing natural landscape, ecological and topographical features of the area for conservation, educational and research purposes and to separate sensitive natural environment such as Country Park from the adverse effects of development. In particular, it is intended to conserve the ecological values of the wetland habitats which form an integral part of the wetland ecosystem. There is a general presumption against development in this zone. In general, only developments that are needed to support the conservation of the existing natural landscape or scenic quality of the area or are essential infrastructure projects with overriding public interest may be permitted.
- 7.8.2 This zone covers the tracts of land stretching from the lowland near Pui O Wan to the valley sandwiched between South Lantau Road and the vegetated slopes of Lantau South Country Park, as well as a contiguous piece of woodland to the west of Shui Hau Wan.
- 7.8.3 New residential development is not permitted within this zone. Redevelopment of existing house may be permitted on application to the Board. The redevelopment of existing house shall not result in a total redevelopment in excess of a maximum plot ratio of 0.4, a maximum site coverage of 25% and a maximum building height of 2 storeys (7.6m), or the plot ratio, site coverage and height of the existing house, whichever is the greater.
- 7.8.4 As diversion of stream, filling of land/pond or excavation of land may cause adverse drainage and environmental impacts on the adjacent areas and the natural environment, permission from the Board is required for such works and related activities except public works co-ordinated or implemented by Government, and maintenance or repair works.
- 7.8.5 The plot ratio under “CA” zone is regarded as being stipulated in an amended statutory plan according to the Joint Practice Note No. 4 “Development Control Parameters Plot Ratio/Gross Floor Area”, and shall be subject to the streamlining arrangements stated therein.

7.9 Coastal Protection Area (“CPA”) : Total Area 93.15 ha

- 7.9.1 This zone is intended to conserve, protect and retain the natural coastlines and the sensitive coastal natural environment, including attractive geological features, physical landform or area of high landscape, scenic or ecological value, with a minimum of built development. It may also cover areas which serve as natural protection areas sheltering nearby developments against effects of coastal erosion. This zone is also intended to safeguard the beaches and their immediate hinterland, and to prevent haphazard ribbon development along the South Lantau Coast. There is a general presumption against development in this zone. In general, only developments that are needed to support the conservation of the existing natural landscape or scenic quality of the area or are essential infrastructure projects with

overriding public interest may be permitted.

- 7.9.2 A long strip of land between the coastline and South Lantau Road stretching from Pui O to Shui Hau including areas adjoining the Country Park area in Chi Ma Wan and Lo Kei Wan is zoned “CPA”. The “CPA” zone also covers sandy shore of the gazetted bathing beaches at Pui O, Cheung Sha and Tong Fuk.
- 7.9.3 New residential development is not permitted within this zone. Redevelopment of existing houses may be permitted on application to the Board. The redevelopment of existing houses shall not result in a total redevelopment in excess of a maximum plot ratio of 0.4, a maximum site coverage of 25% and a maximum building height of 2 storeys (7.6m), or the plot ratio, site coverage and height of the existing house, whichever is the greater.
- 7.9.4 As diversion of stream, filling of land/pond or excavation of land may cause adverse drainage and environmental impacts on the adjacent areas and the natural environment, permission from the Board is required for such works and related activities except public works co-ordinate or implemented by Government, and maintenance or repair works.

7.10 Country Park (“CP”) : Total Area 1,574.31 ha

The intention of this zone is to reflect the Country Park which is to protect the natural features and to provide outlets for outdoor recreation for public enjoyment of the countryside. This zone comprises a major part of Chi Ma Wan Peninsula, Lo Kei Wan Peninsula and Fan Lau. These areas form parts of the Lantau South Country Park, which was first gazetted on 13 January 1978 under the Country Parks Ordinance (Cap. 208). All uses and developments require consent from the Country and Marine Parks Authority and approval from the Board is not required.

## **8. COMMUNICATIONS**

### **8.1 Roads**

- 8.1.1 The Area is mainly served by South Lantau Road, which extends from Mui Wo ferry pier to Shek Pik Reservoir. It continues to Tai O via Keung Shan Road and to Tung Chung via Tung Chung Road. Local areas are served by access roads branching off from South Lantau Road.
- 8.1.2 Since the Area is intended mainly for recreational development, the present restriction on vehicular use of the roads, i.e. only those vehicles possessed with valid Lantau Closed Road Permits are permitted, is still in force.

### **8.2 Footpaths**

The existing footpath system comprises a variety of paved and gently sloping paths and trails connecting villages to South Lantau Road, jetties and other

major activity centres. The footpath system is intended to serve as a link between major activity centres as well as cross-country trails for hikers. Since it is a small-scale plan, the footpath system is not shown on the plan.

### 8.3 Public Transport

Franchised buses, taxis and ferries are the main modes of public transport for the Area. There are ferry services between Chi Ma Wan, Cheung Chau, Peng Chau and Mui Wo. The only ferry pier within the Area is located at Chi Ma Wan Peninsula. Bus services are provided from Mui Wo ferry pier to Pui O, Tong Fuk and Shek Pik, and to Tai O, Tung Chung and Ngong Ping via the Area.

## 9. UTILITY SERVICES

### 9.1 Water Supply

Raw water for the Area is collected at Shek Pik Reservoir. It is then delivered to and treated at Silver Mine Bay Water Treatment Works (located outside the Area) for supply to Mui Wo and Chi Ma Wan; and at Cheung Sha Water Treatment Works for supply to Tong Fuk, Cheung Sha and Pui O. As there is no salt water supply to the Area, mains water is used for flushing purpose.

### 9.2 Sewage Treatment

9.2.1 Currently, there are no sewage treatment facilities in the Area except soakaway pits and septic tanks for most of the village houses. They should only be regarded as an interim solution in remote and low-density areas far away from beaches and fish culture zones.

9.2.2 The over-night accommodation and commercial activities associated with the vast number of weekend and public holiday visitors have already been putting severe pressure for a proper sewage treatment system in the Area.

9.2.3 The Government has planned to implement a sewerage work covering the villages, residential areas and bathing beaches from Shui Hau to Ham Tin. The works proposed comprise village and trunk sewerage system, which include sewage pumping stations, gravity sewers and rising mains, conveying sewage to a new Sewage Treatment Works at Pui O.

### 9.3 Solid Wastes Disposal

Small refuse collection points are located in the vicinity of the villages and residential developments throughout the Area. Domestic wastes delivered to the refuse transfer station in Mui Wo are containerized and shipped to the West New Territories Landfill for disposal.

9.4 Other Services

Electricity supply and telephone service are available in the Area. A telephone exchange is located at Cheung Sha. No difficulty is envisaged to provide electricity and telephone services to meet the need of existing and future developments.

**10. CULTURAL HERITAGE**

- 10.1 Within the boundary of the Plan, there are three declared monuments, i.e. Fan Lau Fort, Stone Circle at Fan Lau and Rock Carving at Shek Pik. There are also seventeen Sites of Archaeological Interest (SAIs) within the Area, namely Cheung Sha Ha Tsuen SAI, Cheung Sha Wan SAI, Chi Ma Wan SAI, Fan Lau Sai Wan SAI, Kau Ling Chung SAI, Ngau Kwu Wan SAI, Pui O SAI, Shap Long SAI, Shui Tseng Wan SAI, Tai Long Wan SAI, Chi Ma Wan, Tai Long Wan SAI, Shek Pik, Tong Fuk SAI, Tong Fuk Miu Wan SAI, Tung Kok SAI, Tung Wan SAI, Shek Pik, Yi Long SAI, and Yi O Fan Lau Boulder Trackway SAI. On 19 March 2009, the Antiquities Advisory Board (AAB) released the list of 1,444 historic buildings. The following historic buildings are also located within the area, namely Cheung Ancestral Hall at Pui O Lo Wai Tsuen (Grade 3), Lin Kong Tong at No. 5 Ham Tin Tsuen (Grade 3), Tin Hau Temple at Fan Lau Miu Wan (Grade 3), Leung Ying Kong Ancestral Hall at Fan Lau Sai Wan Ha Tsuen (Grade 3) and Nos. 49 & 50 Shui Hau (Grade 3). All the declared monuments, sites of archaeological interest and graded/proposed to be graded historic buildings/structures are worthy of preservation.
- 10.2 The AAB also released a number of new items in addition to the list of 1,444 historic buildings. These items are subject to the grading assessment by the AAB. Details of the list of 1,444 historic buildings and its new items have been uploaded onto the official website of the AAB at <http://www.aab.gov.hk>. The locations of the declared monuments and SAIs have been uploaded onto the Geographical Information System on Hong Kong Heritage (<https://gish.amo.gov.hk/>). Details of the declared monuments and SAIs are available for viewing at the Reference Library of Hong Kong Heritage Discovery Centre by appointment.
- 10.3 Prior consultation with the Antiquities and Monuments Office (AMO) should be made if any works, development, redevelopment or rezoning proposal might affect the above declared monuments, SAIs, graded/proposed to be graded historic buildings/structures, new items pending grading assessment, Government historic sites identified by AMO, as well as any other historic buildings/structures identified, both at grade and underground, and their immediate environs. For proposals affecting the SAI(s), the proposals will be considered on a case-by-case basis subject to the archaeological potential of the proposed areas and the level of disturbance to the proposed areas.

## **11. IMPLEMENTATION**

- 11.1 The Plan provides a broad land use framework on which preparation of more detailed non-statutory plans for the Area is based. These detailed plans are used as the basis for planning of public works and reservation of sites.
- 11.2 Future development of the Area will be carried out by both the Government and the private sector. The Government would co-ordinate the provision of public facilities and infrastructure as guided by the planning and development control framework to preserve the natural amenity of the Area and to ensure that development would take place in an orderly manner. The provision of infrastructure will be implemented through the Public Works Programme and the Rural Public Works Programme as and when resources are available. Private developments will be effected principally through private sector initiatives in accordance with the provisions of the Plan.

## **12. PLANNING CONTROL**

- 12.1 The types of permitted developments and uses on land within the Area are listed in the Notes to the Plan. Unless otherwise specified, all building, engineering and other operations incidental to and all uses directly related and ancillary to the permitted developments and uses within the same zone are always permitted and no separate permission is required.
- 12.2 For any land or building falling within the boundaries of this Plan and also falling within the boundaries of the Regulated Area-
- (a) uses of land or building as defined under paragraph (3) in Part B of the covering Notes and which are not in compliance with the terms of the Plan may have adverse impact on the environment, drainage and traffic of the area. Although no action is required to make such use conform to this Plan, any material change of such use or any other development (except minor alteration and/or modification to the development of the land or building in respect of such use which is always permitted) must be always permitted in terms of the Plan or, if permission is required, in accordance with a permission granted by the Board. The Board will consider these applications on their individual merits. Those alteration and/or modification works which may lead to an environmental improvement or upgrading to the Area may be considered favourably by the Board;
  - (b) any development, other than those defined in paragraph (3) in Part B of the covering Notes or in conformity with this Plan or with the permission of the Board, undertaken or continued on or after the material date<sup>1</sup> on land within the boundary of the Regulated Area, may be subject to enforcement and prosecution actions under the Ordinance.
- 12.3 For any land or building falling within the boundaries of this Plan but not falling within the Regulated Area, no action is required to make the existing use of such land or building conform to this Plan, until there is a material

---

<sup>1</sup> Material date means 9 December 2022 as defined in section 1A(1) of the Ordinance

change of use or the building is redeveloped. Any material change of such use or any other development (except minor alteration and/or modification to the development of the land or building in respect of such use which is always permitted) must be always permitted in terms of the Plan or, if permission is required, in accordance with a permission granted by the Board. The Board has published a set of guidelines for the interpretation of existing use in the urban and new town areas. Any person who intends to claim an 'existing use right' should refer to the guidelines and will need to provide sufficient evidence to support his claim. The enforcement of the zoning control mainly rests with the Buildings Department, the Lands Department and the various licensing authorities.

- 12.4 Planning applications to the Board will be assessed on individual merits. In general, the Board, in considering planning applications, will take into account all relevant planning considerations which may include the departmental outline development plans and layout plans for the Area, and Guidelines published by the Board. The outline development plans and layout plans are available for public inspection at PlanD. Guidelines published by the Board are available from the Board's website, the Secretariat of the Board and the Technical Services Division of PlanD. Application forms and guidance notes for planning applications can be downloaded from the Board's website and are available from the Secretariat of the Board, and the Technical Services Division and the relevant District Planning Office of PlanD. Applications should be supported by such materials as the Board thinks appropriate to enable it to consider the applications.

Index of Plan

Plan No. RA/SLC/1 – South Lantau Coast Regulated Area designated under the Town Planning Ordinance (Sheets 1 to 8)

**TOWN PLANNING BOARD**  
**SEPTEMBER 2023**



南大嶼郊野公園  
LANTAU SOUTH COUNTRY PARK

分流西灣  
FAN LAU SAI WAN

分流村  
Fan Lau Tsuen

分流東灣  
FAN LAU TUNG WAN


分流廟灣  
FAN LAU MIU WAN

分流  
FAN LAU

分流角  
FAN LAU KOK

狗嶺涌  
KAU LING CHUNG

位置圖 KEY PLAN



比例 1 : 200 000 SCALE

圖例 NOTATION

 受規管地區  
REGULATED AREA

2023年9月15日按照城市規劃條例第21B條擬備的圖則  
PLAN PREPARED UNDER SECTION 21B OF THE TOWN PLANNING  
ORDINANCE ON 15 SEPTEMBER 2023



Signed Ms Bernadette LINN 雷漢豪女士 簽署  
SECRETARY FOR DEVELOPMENT 發展局局長

依據城市規劃條例指定  
大嶼山南岸受規管地區  
SOUTH LANTAU COAST REGULATED AREA  
DESIGNATED UNDER THE TOWN PLANNING ORDINANCE

比例尺 1 : 10 000 SCALE



圖則編號  
PLAN No. RA/SLC/1 (第一張 共八張)  
(SHEET 1 OF 8)



比例 1 : 200 000 SCALE

圖例 NOTATION

 受規管地區  
REGULATED AREA



2023年9月15日按照城市規劃條例第21B條擬備的圖則  
PLAN PREPARED UNDER SECTION 21B OF THE TOWN PLANNING  
ORDINANCE ON 15 SEPTEMBER 2023

Signed Ms Bernadette LINN 甯漢豪女士 簽署  
SECRETARY FOR DEVELOPMENT 發展局局長

依據城市規劃條例指定  
大嶼山南岸受規管地區  
**SOUTH LANTAU COAST REGULATED AREA**  
**DESIGNATED UNDER THE TOWN PLANNING ORDINANCE**



圖則編號 PLAN No. RA/SLC/1 (第二張 共八張)  
(SHEET 2 OF 8)



比例 1 : 200 000 SCALE

圖例 NOTATION

 受規管地區  
REGULATED AREA



2023年9月15日按照城市規劃條例第21B條擬備的圖則  
PLAN PREPARED UNDER SECTION 21B OF THE TOWN PLANNING  
ORDINANCE ON 15 SEPTEMBER 2023

Signed Ms Bernadette LINN 甯漢豪女士 簽署  
SECRETARY FOR DEVELOPMENT 發展局局長

依據城市規劃條例指定  
大嶼山南岸受規管地區  
**SOUTH LANTAU COAST REGULATED AREA**  
**DESIGNATED UNDER THE TOWN PLANNING ORDINANCE**

比例尺 1 : 10 000 SCALE  
米 METRES 200 0 200 400 600 800 METRES 米

圖則編號 PLAN No. RA/SLC/1 (第三張 共八張)  
(SHEET 3 OF 8)



比例 1 : 200 000 SCALE

圖例 NOTATION

 受規管地區  
REGULATED AREA



2023年9月15日按照城市規劃條例第21B條擬備的圖則  
PLAN PREPARED UNDER SECTION 21B OF THE TOWN PLANNING  
ORDINANCE ON 15 SEPTEMBER 2023

Signed Ms Bernadette LINN 甯漢豪女士 簽署  
SECRETARY FOR DEVELOPMENT 發展局局長

依據城市規劃條例指定  
大嶼山南岸受規管地區  
**SOUTH LANTAU COAST REGULATED AREA**  
**DESIGNATED UNDER THE TOWN PLANNING ORDINANCE**



圖則編號 PLAN No. RA/SLC/1 (第四張 共八張)  
(SHEET 4 OF 8)



比例 1 : 200 000 SCALE

圖例 NOTATION

 受規管地區  
REGULATED AREA



2023年9月15日按照城市規劃條例第21B條擬備的圖則  
PLAN PREPARED UNDER SECTION 21B OF THE TOWN PLANNING  
ORDINANCE ON 15 SEPTEMBER 2023

Signed Ms Bernadette LINN 甯漢豪女士 簽署  
SECRETARY FOR DEVELOPMENT 發展局局長

依據城市規劃條例指定  
大嶼山南岸受規管地區  
**SOUTH LANTAU COAST REGULATED AREA**  
**DESIGNATED UNDER THE TOWN PLANNING ORDINANCE**




圖則編號 PLAN No. RA/SLC/1 (第五張 共八張)  
(SHEET 5 OF 8)



比例 1 : 200 000 SCALE


圖例 NOTATION

 受規管地區  
REGULATED AREA



2023年9月15日按照城市規劃條例第21B條擬備的圖則  
PLAN PREPARED UNDER SECTION 21B OF THE TOWN PLANNING  
ORDINANCE ON 15 SEPTEMBER 2023

Signed Ms Bernadette LINN 甯漢豪女士 簽署  
SECRETARY FOR DEVELOPMENT 發展局局長

依據城市規劃條例指定  
大嶼山南岸受規管地區  
**SOUTH LANTAU COAST REGULATED AREA**  
**DESIGNATED UNDER THE TOWN PLANNING ORDINANCE**



圖則編號 PLAN No. RA/SLC/1 (第六張 共八張)  
(SHEET 6 OF 8)



比例 1 : 200 000 SCALE


圖例 NOTATION





2023年9月15日按照城市規劃條例第21B條擬備的圖則  
 PLAN PREPARED UNDER SECTION 21B OF THE TOWN PLANNING  
 ORDINANCE ON 15 SEPTEMBER 2023

Signed Ms Bernadette LINN 甯漢豪女士 簽署  
 SECRETARY FOR DEVELOPMENT 發展局局長

依據城市規劃條例指定  
 大嶼山南岸受規管地區  
**SOUTH LANTAU COAST REGULATED AREA**  
**DESIGNATED UNDER THE TOWN PLANNING ORDINANCE**



圖則編號 PLAN No. RA/SLC/1 (第七張 共八張)  
 (SHEET 7 OF 8)



比例 1 : 200 000 SCALE

圖例 NOTATION

 受規管地區  
REGULATED AREA

2023年9月15日按照城市規劃條例第21B條擬備的圖則  
PLAN PREPARED UNDER SECTION 21B OF THE TOWN PLANNING  
ORDINANCE ON 15 SEPTEMBER 2023

Signed Ms Bernadette LINN 甯漢豪女士 簽署  
SECRETARY FOR DEVELOPMENT 發展局局長

依據城市規劃條例指定  
大嶼山南岸受規管地區  
**SOUTH LANTAU COAST REGULATED AREA  
DESIGNATED UNDER THE TOWN PLANNING ORDINANCE**

比例尺 1 : 10 000 SCALE  
米 METRES 200 0 200 400 600 800 METRES 米

圖則編號 PLAN No. RA/SLC/1 (第八張 共八張)  
(SHEET 8 OF 8)